



Work Order

WO Date 30/07/2025

WO No. WO -WO- CP&BPL -SBH-KN -2025 - 068-AMD-1

WO Revision 1.00

WO Revision Date 16/12/2025

To,
Reliable Construction Company

P6/24/9/ Ashoka Apprt, sector no 15, New
Panvel Raigad – 410206.
Contact No : 9224383232
Email: cj.chavan487@gmail.com

PAN :No:
GST No: 27AAXPC0195R1ZV
Valid Date: 31/03/2026
Com. Date: 30/07/2025

Company Name :
Classic Promoters and Builders Pvt. Ltd.

Solitaire World, Level - 7, S.No.36/1/1, Opp. Regency
Classic, Mumbai - Bangalore Highway, Pune - 411045.
Site Name : SBH Kalyaninagar
Site Address : SBH- Kalyaninagar
PAN : AABCC1200C
GST No: : 27AABCC1200C1ZN

Subject : Basement Waterproofing at SBH Kalyani Nagar Project.

Site Contact Person :

Dear Sir,

This has reference to your offer submitted to us for SBH Kalyaninagar project and our subsequent negotiation meetings, we are immensely pleased to confirm our intention of awarding the captioned subject work to your esteemed organization on the techno-commercial terms & conditions cum stipulations broadly depicted hereunder in the succeeding paragraphs.

Sr.No	Item Description	Qty	Unit	Rate Rs.	GST%	Amount
1	Basement Waterproofing Breaking RCC Specification : Breaking RCC Shaft 1M3 by breaker and Carting away debris	1.00	Lumsum	5,300.00	18	5,300.00
2	Department labour Specification : Deployed labour for Old MUD cleaning	40.00	Nos	750.00	18	30,000.00
3	Duct shaft waterproofing Specification : Duct shaft bottom waterproofing:: providing all tools equipments labours materials etc and carrying on the work of waterproofing to duct shafts floor work includes removing all debris cleaning applying two coats Black Master liquid membrane laying 112 mm thick brick bat coba finishing top with 50 mm cement sand mortar.	30.00	Sqm	2,400.00	18	72,000.00
4	For Basement Walls Thoroughly cleaning the surface with gri Specification :	150.00	Sq.Mtr	500.00	18	75,000.00
5	For Basement Walls Thoroughly cleaning the surface with gri Specification :	1,260.00	Sq.Mtr	500.00	18	6,30,000.00

	For Basement Walls Thoroughly cleaning the surface with grinders filling all cracks cavities etc with non shrinkage grout, wetting the surface and applying aqua epoxy compound by Choksey STP Ascolite Sikka or equivalent applying two coats of ascofex for gutters only. Guarantee - 10 Yrs					
6	Gutter repairing Specification : B2 gutters repairs excavatio metal soling dewatering.and concreting.Providing all tools equipments labours materials etc and breaking old concrete of B2 gutters excavating soil dewatering laying 150 mm metal soling and concreting in M20 grade concrete curing etc complete.	260.00	Rmt.	1,000.00	18	2,60,000.00
7	leakages by injecting cement and admixtures slurry and pi L Specification :	1,100.00	Nos	800.00	18	8,80,000.00
8	leakages by injecting cement and admixtures slurry and pi L Specification : Arresting existing leakages by injecting cement and admixtures slurry and pi foam material. Make:Sika/Choksey/Pidilite Guarantee - 10 Yrs	200.00	Nos	800.00	18	1,60,000.00
9	PCC M-10 Specification : PCC work for levelling and maintaining slope additional work. Providing all labours materials tools tackles equipments admixtures etc and carrying out the work of laying PCC to low level surfaces at basement 2 near lift room and room below ramp work includes filling the depth with debris and laying 1:3:6 plain cement polymer concrete to proper line and level PCC thickness 75 mm,complete as directed.	130.00	Sq.Mtr	550.00	18	71,500.00
10	PU grouting Specification :	100.00	Nos	1,600.00	18	1,60,000.00
11	PU grouting Specification : Make: Sika101, 201 Guarantee - 10 Yrs	50.00	Nos	1,600.00	18	80,000.00
12	Sealing vertical and horizontal cold joints by making groove Specification :	650.00	Rmt.	650.00	18	4,22,500.00
13	Sealing vertical and horizontal cold joints by making groove Specification : Sealing vertical and horizontal cold joints by making grooves and filling with special formulated sealant Guarantee - 10 Yrs	1,800.00	Rmt.	650.00	18	11,70,000.00
14	Tractor Trip Specification : additional work Tractor trips: providing tractor for carting away debris etc from B2 including loading tractor.	10.00	Nos	1,500.00	18	15,000.00
15	Treatment for gutters Specification :	53.19	Sq.mtr.	1,000.00	18	53,190.00

16	UG water tank Repairs Specification : UG water tank; Repairs to side walls and bottom slab of tank with replastering and laying PCC at bottom making wattas at junction with polymer modified mortar and applying two coats of Aqua epoxy Techoxy by Choksey Dr Fixit Ascolite or equivalent. Guarantee - 10 Yrs	250.00	Sq.Mtr	1,000.00	18	2,50,000.00
	Basement Waterproofing					

				Contract Amount (A)	43,34,490.00
				CGST 9% RD	3,90,104.10
				SGST 9% RD	3,90,104.10
				Total GST (B)	780,208.20
				Total (A + B)	51,14,698.00

AMOUNT IN WORDS:

RUPEES FIFTY-ONE LAC FOURTEEN THOUSAND SIX HUNDRED NINETY-EIGHT ONLY.

WO Terms And Conditions :

- 1.General :** Any dispute arising out of Local conflict shall be the sole responsibility of the Contractor & the consequences arising out of the same shall needs to be effectively handled by the Contractor including necessary interaction to be made With Local administrative authorities, an aid for its settlement, etc. complete.
- 2.Definitions as applicable to this contract :** Owner / Employer shall mean M/s. Classic Promoters & Builders Pvt Ltd. and shall include their legal representatives, assigns or successors. Contractor shall mean M/s. Reliable Construction Company and shall include their legal representatives, assigns or successors.
- 3.Duration of Work :** Time is the essence of this Contract. Contractor shall complete the entire scope of work within mutually agreed period from the date of readiness & handover the site to the Contractor for Work.
- 4.Payment terms :** 20% mobilization advance along with work order against Corporate Guarantee along with undated cheque of equivalent amount.
Balance Payment after completion of work & within 30 days after submission of certified copy of tax invoice in prescribed format with the required back up at Solitaire Head Office.
- 5.Mode of Measurement :** As per IS 1200.
- 6.Water & Electricity :** One-point supply in Owner's Scope & its further distribution as per site requirement shall be in Contractor's scope
- 7.Safety :** Contractor shall ensure that all your Workmen are provided with adequate safety equipment (i.e., PPE – Personal Protective Equipment's with full body harness – which shall largely comprise of IS branded Safety belts, Helmets, etc.) While working Any injury or accident caused to your Workmen will be your sole responsibility and the Consultant(s) / Owner(s) shall not be held responsible for the same.
- 8.Quality :** The Contractor shall strictly adhere to & comply to the quality desired by the Owner and failing to which the Owner reserves right to take the necessary actions including the levy of debits, etc. or as deemed suitable by the Owner. Any inferior quality work as pointed out from time to time by EIC shall be made good by the Contractor at his own expenses & no extra payment shall be made to the Contractor for such activity. All the works to be executed shall be strictly as per the Item Specification, Material Specifications and as per mentioned by the Owner & no deviations in the same shall be accepted.
- 9.Labour :** Labours for all the activities to be arranged and borne by contractor with the necessary required supervision including their food arrangements and accommodation.
- 10.Indemnity :** The Contractor shall indemnify Owner (s) with his complete Site Staff & staff at the back office as well and hold them harmless against all claims arising out of royalties of materials, taxes and patents payable by the Contractor, compensation payable by the Contractor to their sub-Contractors / personnel, etc. and losses, damages occurred to third party due to Contractors act of sheer negligence or carelessness , accidents/ fatal accidents or any other cause connected with the execution of work under this awarded contract till the entire period of this work.
- 11.Insurance and Statutory Compliance :** Workmen Compensation, insurance of Workmen, third party liability insurance cover and all other relevant insurances including Strict observance of PF+ ESIC and labour laws as deemed applicable to this contract shall be under the scope of the Contractor.
- 12.Jurisdiction :** All disputes arising out of or in connection with this Work Contract shall be deemed to have arisen at Pune

and only Courts in Pune shall have an exclusive jurisdiction to determine the same.

13.Liquidated Damages:

a) Contractor shall be obliged to complete the contractual scope within the contractual time frame.

a 1) In the event of failure of Contractor to complete the work within the stipulated time period due to reasons solely attributed to the Contractor, the contractor shall be liable to pay a liquidated damages at the rate of 2% (Two percent) of the total contract value per week of delay.

a 2) Maximum Liquidated damages shall not exceed 5% of total Contract Value.

b) Contractor Shall not be relived from the obligations even in the event of applicability of the said LD, Contractor shall complete the balance work within the time as mutually agreed further by both the parties.

c) Any delay attributed to Force Majeure shall not be accounted for while evaluating the repercussion under the clause of Liquidated damages as well as while calculating the incentive as well.

d) Similarly, in the event if the cause of delay is solely attributed to the owners cause then same shall be recorded and the necessary time extension will be given to the Contractor.

14.Force Majeure :

For the purpose of this Contract, a force majeure event shall mean an event like An act of god or events beyond the reasonable control of the affected party which could not have been expected to occur, exceptionally adverse weather conditions, lightning, earthquake, cyclone, flood, volcanic eruption, landslide or fire which prevent the Party claiming force majeure (“affected party”) from performing its obligations under this Contract and which act or event is

a. beyond the reasonable control of and not arising out of the fault of the affected party and

b. the affected party is unable to overcome such act or event by exercise of due diligence, reasonable efforts, skill, and care and

c. has a material adverse effect on the Work.

15.Defect Liability Period :

The defect liability period shall be 12 calendar months (which shall include one monsoon) starting from the date of handing over and upon issuance of completion certificate by owners EIC

16.Termination :

In the event if the Contractor categorically fails to satisfy the Owner’s EIC / Principal Contractor with regards to overall quality of the work executed / being executed, deployment of resources in adequate numbers, overall speed of the work & finally about overall completion of the Project, etc. then the Owner reserves the full rights to terminate the contract without assigning any reason by issuing termination 2 no’s (two) notices each of 7 days in advance.

On such termination, Contractor should be obliged to stop the work and vacate the premises within the stipulated time frame and the Owner is obliged to pay the dues in such stipulated time as agreed by the contractor & towards the work executed till date.

17.Retention :

5% Retention shall be deducted from each R.A. Bill / Payment and same shall be withheld till Defect liability period and as per instruction by the EIC of Owner.

18.Others :

Escalation: Rates hereby mentioned in Bill of Quantities shall remain unaltered & unchanged & thus mandatorily binding upon the contractor for entire scope of work awarded herewith (to make Basement 01 & 02 Leakage Free) & till the complete tenure of the Contract including time extension if any, Contractor is not liable to claim any escalation whatsoever under any circumstances.

Approved by digitally with the concern of

Name	Date/Time	Current Status	Remarks
Contracts Head(vikas.jadhav)		Approved	ok

Zeeshan Jalil **For Classic Promoters and Builders Pvt. LtdFor Reliable Construction Company**

Created By **Approved By** **Authorized Signatory** **Authorized Signatory**

30/07/2025 11:23:3